

Tele : 7307014127
Email ID : armypublicschoolkgt@gmail.com
Website : <https://apsgorakhpur.org.in/>

Army Public School
Gorakhpur – 273008

10209/Proj/APSG

18 Sep 2024

(Vendor Concerned)

**CALLING OF QUOTATIONS FOR INSTALLATION OF OLD CEILING FANS
IN ACTIVITY SHED OF ARMY PUBLIC SCHOOL, GORAKHPUR**

Sir/Madam,

1. Army Public School, Gorakhpur is interested for 'Installation of old ceiling fans in activity shed of APS Gorakhpur'.
2. The details of technical specification / scope of work is as per **Appendix – 'A'** attached to this letter/tender form.
3. You are requested to submit your quotation as per technical specification in a sealed envelope (duly quoted **QUOTATION FOR INSTALLATION OF OLD CEILING FANS IN ACTIVITY SHED**) and drop in quotation box placed at Main Gate No - 2 of Army Public School, Gorakhpur by 1700 hrs on 04 Oct 2024. Quotation must be on proper letter head of firm with GST Number (Certificate), Office Seal and Rates should be **GST Inclusive**.
4. The school reserves its right to alter the quantities/terms of reject any quotation without assigning any reasons whatsoever. TDS will be applicable as per prevailing Govt rules & E-way bill required for transaction of more than Rs 50,000/-.
5. Works to be done against a supply order. Payment will be released by cheque once the works completed and checked for correctness on ground by a separate Board of Officers/Teachers.
6. Minimum warranty of work will be 01 year from the date of completion of work.


Yours faithfully,


(Dr Vishal Tripathi)
Principal


Enclosures : As above.


TECHNICAL SPECIFICATION /SCOPE OF WORK**INSTALLATION OF OLD CEILING FANS IN ACTIVITY SHED
OF ARMY PUBLIC SCHOOL, GORAKHPUR**

1. Total No. of Iron Bars 15.
2. Five Fans to be fitted in each iron bar with proper balance distance.
3. Wiring will be done with 01 mm wire.
4. All the wires will be covered with plastic pipe and flexible pipe where required.
5. Plastic and flexible pipe to be tied with plastic tie.
6. Where ever electric joint is there it must insulated with tape.
7. 75 Fan Clump to be used with proper washer and nut bolt.
8. 75 No of fans will be divided into four parts of circuit break with proper board and MCB.
9. 75 new condenser will be used.
10. Fan servicing (Cleaning and Greasing) including labour charges from starting to ending work.
11. 120 new fan bearing to be used as per requirement.

(a) Presiding Officer : 
(Mrs Shashi Kumari, PGT)
APS Gorakhpur

(b) Members (i) : 
(Mrs Saroj Singh, TGT)
APS Gorakhpur

(ii) : 
(Mr Avinash Kumar, TGT)
APS Gorakhpur

(iii) : 
(Mr Rajesh Dubey, Bio Lab Attd)
APS Gorakhpur

COUNTERSIGNED


PRINCIPAL
Army Public School
Gorakhpur